

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-22742-00-00
Spot: NESENW Sec/Twnshp/Rge: 32-33S-6E
3658 feet from S Section Line, 3006 feet from E Section Line
Lease Name: BERRY Well #: OUR #6
County: COWLEY Total Vertical Depth: 3042 feet

Operator License No.: 34470
Op Name: VICTORY MINERALS LLC
Address: PO BOX 414931
KANSAS CITY, MO 64141

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	208		100 SXS CMT
PROD	4.5	3034		100 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/17/2012 12:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: CARMON DECKER Company: VICTORY MINERALS Phone: (816) 223-3712

Proposed Plugging Method: AS PER DISTRICT #2 RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 01/18/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

JUNK IN HOLE, RIH ON WIRELINE SET CIBP @ 286'. RIH ON WIRELINE PERFORATED SQUEEZE HOLES @ 284'-285'. RIH WITH TBG @ 285', GRESSEL OILFIELD SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED INSIDE & ON BACKSIDE IF 4-1/2" CASING. PLUG DOWN 12:30 PM 1-18-2012. GRESSEL OILFIELD CEMENT TICKET #38862.

Perfs:

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)

RECEIVED
FEB 03 2012
KCC WICHITA

✓ 2/23/12

12K