

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-22965-00-00
Spot: NENENW Sec/Twnshp/Rge: 32-33S-6E
4973 feet from S Section Line, 3007 feet from E Section Line
Lease Name: BERRY Well #: OUR #8
County: COWLEY Total Vertical Depth: 3030 feet

Operator License No.: 34470
Op Name: VICTORY MINERALS LLC
Address: PO BOX 414931
KANSAS CITY, MO 64141

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	203		90 SXS CMT
PROD	4.5	3030		100 SXS CMT

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/17/2012 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: CARMON DECKER Company: VICTORY MINERALS LLC Phone: (816) 223-3712

Proposed Plugging Method: AS PER KCC DISTRICT #2 RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 01/18/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

JUNK IN HOLE, RIH ON WIRELINE SET CIBP @ 297'. RIH ON WIRELINE PERFORATED SQUEEZE HOLES @ 290'-291'. RIH WITH TBG @ 295', GRESSEL OILFIELD SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 115 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED INSIDE & ON BACKSIDE OF 4-1/2" CASING. PLUG DOWN 1:30 PM 1-18-2012. GRESSEL OILFIELD CEMENT TICKET #38863.

Perfs:

Top	Bot	Thru	Comments
2982	2992	CSG	

RECEIVED
FEB 03 2012
KCC WICHITA

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)

✓ 2/03/12

1/4