

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20763-00-00
Spot: S2S2NENE Sec/Twnshp/Rge: 16-35S-26W
1100 feet from N Section Line, 660 feet from E Section Line
Lease Name: MATHEWS Well #: 1-16
County: MEADE Total Vertical Depth: 6490 feet

Operator License No.: 8060
Op Name: ZENERGY, INC.
Address: 6100 S YALE STE 1700
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5900		WITH 2 SX CMT
CIBP		6187		
CIBP		6440		
SURF	8.625	580		WITH 300 SX CMT
COND	20	128		8 SX
PROD	5.5	6484	1997	WITH 200 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 01/16/2012 1:00 PM
Plug Co. License No.: 8733 Plug Co. Name: DUNKIN, JERRY, INC.
Proposal Rcvd. from: BUTCH DUNKIN Company: DUNKIN, JERRY, INC. Phone: (580) 237-6152

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 01/16/2012 3:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CIBP @ 5900' WITH 2 SX CMT. HEAVY MUD BETWEEN PLUGS. 1ST PLUG AT 1820' WITH 50 SX CMT. 2ND PLUG AT 900' WITH 50 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6410	6418		
6055	6094		
6004	6008		
5967	5970		

RECEIVED
FEB 03 2012
KCC WICHITA

Remarks: USED CLASS H CEMENT W/2% CC BY JERRY DUNKIN INC.

Plugged through: CSG

District: 01

RECEIVED

JAN 24 2012

KCC DODGE CITY

Signed



(TECHNICIAN)

2/03/12
Form CP-2/3