

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-20193-00-00
Spot: NESW Sec/Twnshp/Rge: 2-17S-24W
1967 feet from S Section Line, 1961 feet from W Section Line
Lease Name: HORCHEM D Well #: 3
County: NESS Total Vertical Depth: 4493 feet

Operator License No.: 33190
Op Name: NOBLE ENERGY, INC.
Address: 1625 BROADWAY, STE 2200
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1700		WITH 2 SX CMT
SURF	8.625	221		WITH 150 SX CMT
PROD	5.5	4488	0	WITH 75 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/16/2012 9:30 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: TOM KARST Company: NOBLE ENERGY Phone: (281) 872-3100

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 50 SX CMT & 200# HULLS. PULL TBG & RUN CIBP TO 1700' WITH 2 SX CMT. PRESSURE TO 1500#. IF HOLDS PERFORATE @ 950' & PUMP 80 SX CMT OVER CASING VOLUME, THEN 150 SX CMT DOWN BACKSIDE IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/16/2012 4:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

WELL HAS BEEN SQUEEZED AT 2794-2858' W/300 SX CMT, 3044-3354' W/300 SX CMT, 3182-3485' W/300 SX CMT RUN TBG TO 4448' & PUMP 50 SX CMT & 200# HULLS. PULLED TBG & SET CIBP @ 1700' WITH 2 SX CMT. PRESSURED CASING TO 1800# & HELD. PEFORATED AT 940' & PUMP 165 SX CMT. MAXIMUM PRESSURE 400#. SHUT IN PRESSURE 400#. TIED ONTO BACKSIDE & PUMPED 75 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4488	4493	OH	

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: TBG

RECEIVED
FEB 03 2012
KCC WICHITA

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
JAN 24 2012
KCC DODGE CITY

Form CP-20

2/03/12