

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-23417-00-00  
Spot: NWNESESW Sec/Twnshp/Rge: 4-32S-10W  
2411 feet from S Section Line, 2077 feet from W Section Line  
Lease Name: ROWE A Well #: 1  
County: BARBER Total Vertical Depth: 4943 feet

Operator License No.: 33235  
Op Name: CHIEFTAIN OIL CO., INC.  
Address: 605 S. 6TH; PO BOX 124  
KIOWA, KS 67070

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4360		WITH 2 SX CMT
SURF	8.625	348		WITH 215 SX CMT
PROD	5.5	4937	3100	WITH 200 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/11/2012 11:45 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Revd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4360' & 2 SX CMT. PLUG AT 660' WITH 15 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/11/2012 12:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4360' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 378' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4426	4432		
4412	4422		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed

Stephen J Pfeifer  
(TECHNICIAN)

RECEIVED

JAN 24 2012

KCC DODGE CITY

RECEIVED  
FEB 03 2012

KCC WICHITA

Form CP-2

2/03/12