

15-171-20057-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAY 29 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Thunderbird Drilling Company, Incorporated,

Complete Address Box #18407, Wichita, Kansas.

Lease Name Miller Well No. J-1

Location C1W-SE Sec. 16 Twp. 20 Rge. (E) (W) 33

County Scott Total Depth 4800'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor B C B Drilling, Incorporated,

Address 720 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour 11:15 PM Day 24 Month 5 Year 1973

The above well was plugged as follows:

679'--8 5/8" Surface casing, cement circulated with 300 Sx.
Top of Dakota section @ 675'.

Circulated hole with heavy mud. Pulled DP to 960' and displaced 140 Cu. Ft. cement
thru DP from 960' to 450'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu.
Ft. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Deholl
Well Plugging Supervisor

INVOICED

DATE 5/31/73
INV. NO. 7431-44