

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 60-29

LOCATION C-SF-7E

SEC. 15 TWP. 20 RGE. 33-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Vanniman

Operator Shallow Water Refs. Co. Address 114 W. Pine - Garden City - Kans.

Field _____ County Scott

Total Depth 4699 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe left in Hole - 1 1/2" - 243ft - Circulated with cement.
Plugged back lower bottom to 4550ft - Rock Bridge x 10 sacks
& cement at 4550ft - Shot off & Pulled 8 1/2" casing - mud to 3700ft
Rock Bridge x 10 sacks cement at 3700ft - Shot off & Pulled the
10 3/4 casing - Mud to 1400ft - Rock Bridge x 10 sacks cement -
at 1400ft - Mud to 256ft - Rock Bridge x 50 sacks cement.
at 256ft - Mud to 20ft - Bridge x 10 sacks of cement at the
surface

Pipe Pulling - Inc. Stafford - Kans

Plugging - Contractors -

C. M. Stough
District Conservation Agent 12-20-48

Date 12-22-48

PLUGGING
FILE SEC 15 T 20 R 33
BOOK PAGE 60 LINE 29