

15-171-20004-00-00

Form CP-3  
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
AUG 16 1967

Operator's Full Name Mallonee-Coppinger Operations, Incorporated,

Complete Address: 1207 Union National Building, Wichita, Kansas.

Lease Name Beach Well No. 1

Location Appr. CSW-SE Sec. 26 Twp. 20 Rge. (E) (W) 33

County Scott Total Depth 4935

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Mahoney Drilling Company, Incorporated,

Address: Box #1257, Liberal, Kansas. License No.     

Operation Completed: Hour 1:00AM Day 12 Month 8 Year 1967

The Above well was plugged as follows:

295'--8 5/8" Surface pipe, cement circulated with 275 Sx.  
Dakota section from 692' to 907'.

Circulated hole with heavy mud. Pulled DP to 925' and displaced 110 Sx.

cement thru DP. Pulled DP to 300' and displaced 20 Sx. cement thru DP.

Pulled DP. set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. F. J. J. J.  
Well Plugging Supervisor

DATE 8/16/67

INV. NO. 6152-W