

15-171-30006-00-00

Form CP-3
Rev. 6-26-62

10

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC - 6 1965

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Colorado Oil and Gas Corporation,

Complete Address: P.O. Box # 158, Liberal, Kansas.

Lease Name Dague Well No. 1-24

Location C1W-SE Sec. 24 Twp. 20 Rge. (E) (W) 33

County Scott Total Depth 2716

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Sargents Casing Pulling,

Address: P.O. Box #506, Liberal, Kansas. License No. 511

Operation Completed: Hour 5:00PM Day 2 Month 12 Year 1965

The Above well was plugged as follows:

343'--7" Surface pipe, cement circulated.
2715'--4 1/2" Production casing cemented with 100 Sx. Top of cement @ 2125'
(Temperature Survey). Top perforations from 2643' to 2680'.

Squeezed bottom of hole with 20 Sx. cement, left plug @ 2500' WLM .
Pulled 4 1/2" to 660' and circulated heavy gel mud. Pulled 4 1/2" to 600' and
displaced 20 Sx. cement thru 4 1/2". Pulled 4 1/2" to 300' and displaced 20 Sx.
cement thru 4 1/2". Pulled 4 1/2" set bridge @ 35' and filled to bottom of
cellar with 5 Sx. cement.

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 12/6/65

INV. NO. 2334-W