

15-171-20003-00-00

KANSAS

Form CP-3
Rev. 6-26-62

210

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
AUG 31 1967
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Mallonee; Coppinger Operations, Incorporated,

Complete Address: 1207 Union National Building, Wichita, Kansas.

Lease Name Petro Well No. 1

Location Appr. CHE-IW Sec. 23 Twp. 20 Rge. (E) (W) 33

County Scott Total Depth 4720'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Mahoney Drilling Company, Incorporated,

Address: Box #1257, Liberal, Kansas. License No. _____

Operation Completed: Hour 9:00PM Day 27 Month 7 Year 1967

The Above well was plugged as follows:

296'--8 5/8" Surface pipe, cement circulated with 275 Sx.
Dakota section from 565' to 670'.

Circulated hole with heavy mud, set plug thru DP from 695' to 465' with 85 Sx.
cement. Pulled DP to 315' and set plug thru DP from 315' to 296' with 20 Sx.
cement. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7/31/67
INV. NO. 6040-W

Signed: M. L. Dehels
Well Plugging Supervisor