


15-169-00451-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Saline County, Sec. 7 Twp. 15 Rge. (E) 2 (W)  
Location as "NE/CNW/SW" or footage from lines C E/2 NW NE  
Lease Owner Santa Fe Pipe & Supply, Inc.  
Lease Name Riddle Well No. 1  
Office Address Box 562, Great Bend, Kansas 67530  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 19\_\_\_\_  
Application for plugging filed 19\_\_\_\_  
Application for plugging approved 19\_\_\_\_  
Plugging commenced May 29 19 73  
Plugging completed May 31 19 73  
Reason for abandonment of well or producing formation depleted  
If a producing well is abandoned, date of last production 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3232 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			279'	8 5/8"	279'	none
			3229'	5 1/2"	3229'	2580.06

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded back to 3190' and dumped 5 sacks of cement.

Set 10' rock bridge at 300'. Plugged well with 40 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 5 1973

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor PIPE PULLERS, INC.  
Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Evelyn Roth (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth  
Ellinwood, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of June 19 73

Feb. 10, 1975

George A Meyer  
Notary Public.



DRILLER LOG

Company: Solar Oil Company  
Farm: Riddle # 1  
Commenced: June 9, 1961

E/2 NW NE Section 7-15-2W  
Saline County, Kansas  
Completed: June 18, 1961

Elevation:

-----

0 - 60	sand
60 - 100	shale
100 - 1170	lime & shale
1170 - 1600	shale & lime
1600 - 1920	lime & shale
1920 - 2024	shale & lime
2024 - 2445	lime
2445 - 2685	lime & shale
2685 - 2880	Mississippi
2880 - 2954	lime
2954 - 3046	shale
3046 - 3232	lime
3232	Total Depth

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 30 1973  
CONSERVATION DIVISION  
Wichita, Kansas

Set 80 feet of 13 3/8 inch conductor pipe. Cemented with 95 sacks of cement with 2% gel and 4% calcium chloride. Set 279' of 8 5/8" surface pipe. Cemented with 200 sacks of cement with 2% gel and 2% calcium chloride.

Tops:

<del>Lansing K.C.</del>	-	<del>2024'</del>
<del>Mississippi</del>	-	<del>2685'</del>
<del>Hunton</del>	-	<del>3046'</del>
<del>Maquoketa</del>	-	<del>3228'</del>

Ran ~~3232~~<sup>3129</sup> feet of 5 1/2" casing. Cemented with 75 sacks of cement.

A F F I D A V I T

STATE OF KANSAS )  
                              ) SS  
COUNTY OF BARTON )

I, Allan Harms of the Harms-Burt Drilling Company being first duly sworn on oath state: I have knowledge of the facts, statements and matters herein contained and the same are true and correct.

Allan Harms

Subscribed and sworn to before me this 7 day of July, 1961.

Mary E. Van Pelt  
Notary Public

My commission expires January 20, 1962.