

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-169-19072-00-00

API NUMBER N/A

LEASE NAME Swigart

WELL NUMBER #2

C E/2 Ft. from S Section Line

W/2 SE Ft. from E Section Line

SEC. 6 TWP. 15 S RGE. 2 (E) or (W)

COUNTY Saline

Date Well Completed 11-29-61

Plugging Commenced 10-8-84

Plugging Completed 11-15-84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Multistate Oil Properties

ADDRESS 3000 United Founders Blvd., Okla. City, OK:

PHONE#(405) 848-8551 OPERATORS LICENSE NO. 5415

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #5, 2501 Market Place, Suite D, Salina, KS, 67401

Is ACO-1 filed? No If not, is well log attached? Sent in with CP-1.

Producing Formation Maquoketa Depth to Top 3229' Bottom 3234' T.D. 3234'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi	Lime - Shale		235	8-5/8"	10-23-61	None
Maquoketa	Lime - Shale		3229	5-1/2"	11-09-61	2300' 11-13-84

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
MIRU PU. TIH w/Halliburton EZSV cement retainer & set @ 3183'. Load tbg. & annulus w/fresh wtr. Set btm. plug w/75 sx. 60/40 poz, left 2 sx. on top of retainer. TOOH w/tbg. RDMO PU. Shot csg. & recovered 2300' of 5-1/2" csg. Set top plug as follows: pump 20 sx. gel, 3 sx hulls drop wood/rubber plug, pump 125 sx. 50/50 poz. Final pressure 450 psi. Plugging complete.  
(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Kelso Casing Pullers License No. 6050

Address Chase, Kansas

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Deborah K. Gandy (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Deborah K Gandy  
3000 United Founders Blvd.  
(Address) Oklahoma City, Okla. 73112



SUBSCRIBED AND SWORN TO before me this 21st day of January, 19 85

CONSERVATION DIVISION  
Wichita, Kansas

Karen A. Kemler  
Notary Public

Notary Commission Expires: May 7, 1985