

15-169-00169-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Saline County, Sec. 5 Twp. 15 Rge. 2 W (E) (W)
Location as "NE/CNW&SWK" or footage from lines # C NW NE
Lease Owner L. B. Jackson
Lease Name Dan Mayer Well No. I
Office Address 4609 East 31st Tulsa, Oklahoma 74135
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed II-27 1956
Application for plugging filed 8-6 1972
Application for plugging approved 8-7 1972
Plugging commenced 8-21 1972
Plugging completed 9-6 1972
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3273' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		50'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pumped 25 bx of Aqua Jel Mud and 150 bx of Portland cement, down 8" casing with Halliburton Cementing Co. Max Pressure 1500# and Min standing pressure 400#.

RECEIVED
STATE CORPORATION COMMISSION
SEP 13 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb
2809 King St. Hutchinson, Kansas 67501
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of September, 1972

My commission expires January 5, 1974
Notary Public


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas

15-169-00169-00-00
SEC. 5 T. 15 R. 27
C. 17 NE

Company- DE WEFSE & SANDERSON
Farm- Don Myer No. 1
Don Myer

Total Depth. 3273'
Comm. 11-10-56 Comp. 11-27-56
Shot or Treated.
Contractor.
Issued. 2-2-57

County Saline
KANSAS



CASING:
5 5/8" 2290' cem. 200
5 1/2" 3270'

Elevation. 1315'

Production. 20 Bbls

Figures indicate Bottom of Formations.

clay	70
sandy shale	80
shale	225
lime	290
lime & shale	510
lime	770
shale, shells	1300
lime & shale	1370
shale	1460
shale, shells	1545
lime, shale	1635
lime	1800
shale & lime	1850
shale	2004
lime	2006
shale	2075
lime	2595
lime & shale	2678
Conglomerate	2690
Mississippi	2760
Mississippi	
Chert & lime	2825
Mississippi	
lime	2909
shale	2920
Mississippi	2940
lime & shale	3000
shale	3090
lime	3190
lime & shale	3220
shale	3273
Total Depth	

TO S	
Lansing	2074
Conglomerate	2678
Mississippi	2720
Hunton	3085
Viola	3270

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1972
CONSERVATION DIVISION
Wichita, Kansas