


15-169-00444-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Saline County. Sec. 5 Twp. 15 Rge. 2 N (E) (W)
Location as "NE/CNW/SW" or footage from lines C N/2 NE/4
Lease Owner L. R. Jackson
Lease Name Don Myers Well No. 2
Office Address 4609 East 31st St. Tulsa, Oklahoma 74135
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 11-23 19 72
Application for plugging filed 8-6 19 72
Application for plugging approved 8-7 19 72
Plugging commenced 8-22 19 72
Plugging completed 11-23 19 72
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Tanna
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3284' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		2,754'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3284' to 3270'. Dumped 3 ex of cement. Mudded hole to 215'. Made 15' of rock bridge. Dumped 3 Yrds. of Ready-Mix Cement, filling to the bottom of the cellar.

RECEIVED
STATE CORPORATION COMMISSION

AUG 29 1972

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Rego, ss.

Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb
2809 King St. Hutchinson Kansas 67501
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of August, 19 72

My commission expires January 5, 1974

Judy Lamb
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

503 East Murdock,

Wichita, Kansas

15-169-00444-00-00

Company: DE WESSE-SANDERSON
 Farm: Don Myor No. 2

SEC. 5 T. 15 R. 2W
 CN/2 NE/4

Total Depth. 3284'
 Comm. 11-14-57 Comp. 11-23-57
 Shot or Treated.
 Contractor. J. A. Molland Drilling Co.
 Issued. 2-22-58

County Saline KANSAS



CASING:

8 5/8" @ 205' cem. w/135 sx.
 4 1/2" @ 3282' cem. w/50 sx.

Elevation. 13181 RB

Production. 25 DOPD

Figures indicate Bottom of Formations.

surface soil & clay	40
clay & shale	50
sand	75
shale & shells	160
gypsum & lime	205
gypsum, lime & shale	265
gypsum & lime	320
shale & shells	565
lime & shale	650
lime	790
shale & lime	1400
shale & shells	1580
lime & shale	1920
sandy shale	2010
shale & lime	2085
lime	2260
lime & shale	2709
Mississippi lime	2990
shale & shells	3100
lime	3225
shale & shells	3280
dolomite	3284
Total Depth	RTD

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 7 1972
 CONSERVATION DIVISION
 Wichita, Kansas

TOPS: (Scout)	
Kansas City	2085
Mississippi	2720
Maquoketa Dolomite	3280