

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-171-19049-00-00
API NUMBER Pre 1967

LEASE NAME Vaniman

WELL NUMBER #2

SPOT LOCATION NE NE

SEC. 15 TWP. 20 RGE. 33 (N) or (W)

COUNTY Scott

Date Well Completed 3-22-45

Plugging Commenced 7-23-84

Plugging Completed 7-26-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR The Maurice L. Brown Co.

ADDRESS 200 Sutton Place, Wichita, Ks. 67202

PHONE (316) 265-4651 OPERATORS LICENSE NO. 6234

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Ks.

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation Miss. Depth to top 4605 bottom 4660 T.D. 4660

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface				10 3/4"	265'	0'
Production				5 1/2"	4618'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Set CIBP @ 4410' w/2 sks. cement
Pumped 2 sks. hulls & 25 sks. cement to 1900' Displaced w/mud to 1200'
Pumped 25 sks. cement 1200' to 1025' Displaced w/mud to 300'
Pumped 25 sks. cement 300 to 150' Displaced w/mud to 50'
Put bridge & 10 sks. 50' to 0'
Cut off 10 e/4" 3' below ground level
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497
Address Box F, Sublette, Ks. 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well is correct that the same are true and
correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION
(Signature) Edgar J. Eves
(Address) Box F, Sublette, Ks. 67877



AUG 29 1984
SUBSCRIBED AND SWORN TO before me this 30th day of July, 1984
Wichita, Kansas

Sondra L. Eves
Notary Public

My Commission expires: 12-6-84

