

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-171-19055-00-00

API NUMBER NONE  
LEASE NAME Pile  
WELL NUMBER 3  
SPOT LOCATION C-E/2 SW/4  
SEC. 14 TWP. 20 RGE. 33 (EN or (W))  
COUNTY Scott  
Date Well Completed 1938  
Plugging Commenced 3-4-1987  
Plugging Completed 3-11-87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR The Maurice L. Brown Co.  
ADDRESS 200 Sutton Place Bldg.; Wichita, Ks. 67202

PHONE # (316) 265-4651 OPERATORS LICENSE NO. 6234

Character of Well SWD  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation Marm. Depth to top 4264 bottom 4297 T.D. 4686

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				13 3/8"	205'	0'
Production				7"	4624'	90'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pump 50 sks. cement 1540' to 1447' - Shot 7" @ 1352' - Ran tubing to 1347' and pumped 50 sks. cement to seal - Top of cement 850' - Halliburton pumped 450 sks. of Halco Light from top.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497  
Address Box F, Sublette, Ks. 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves (~~XXXXXXXXXXXXXXXXXXXX~~) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filled out that the same are true and correct, so help me God.

(Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks. 67877

MAR 31 1987

SUBSCRIBED AND SWORN TO before me this 23 day of March, 1987

My Commission expires: 12-6-88

Sonora L. Eves  
Notary Public



## LOG OF PILE WELL NO. 3

C E $\frac{1}{2}$  S $\frac{1}{4}$  Section 14-20S-33"  
Scott County, Kansas

Surface Elevation: 2947'

Rotary with cable tool completion. Commenced: 7-18-38 Completed: 9-13-38

Set 13 3/8" surface pipe at 205' with 200 sacks cement.  
Set 7" casing at 4624' with 100 sacks cement.

Figures indicate bottom of formations:

surface clay	40	shale, lime & shells	2700
sand	95	lime & shale	2765
lime & shale	130	sandy lime	2815
sand	180	shale & lime	2885
lime & shale	205	lime	2935
shale	240	red bed & lime	2955
lime	330	lime	2965
shale	500	red bed & lime	2973
sandy shale	585	shale & lime	3079
shale & shells	725	lime	3130
sandy shale	745	cherty lime hard	3151
sandy lime & shale	765	chert & lime	3153
shale	830	red bed	3195
shale & shells	870	lime	3205
sand	890	lime hard	3269
shale	895	lime	3844
sandy shale	940	lime hard	3909
sand	955	lime	4210
shale & shells	1070	limehard	4226
sand	1105	broken lime	4240
shale	1115	lime	4365
sandy shale	1200	lime hard	4370
red bed & shale	1230	sandy lime	4400
red bed	1395	lime	4440
shale & shells	1470	lime hard	4483
shale	1525	lime & chert	4497
red bed & shale	1615	lime	4537
red bed & salt	1730	sand & shale	4554
sand	1750	sand	4558
red bed & sand	1780	lime	4566
shale & red bed	1868	shale	4570
shale, red bed & shells	2090	sandy shale	4577
shale	2165	sand & chert	4578
shale sticky	2240	lime & chert	4583
red bed, shale & shells	2340	lime	4586
shale & red bed	2360	lime	4588
shale	2455	sand & lime	4596
shale & lime	2590	lime	4625
sand & lime	2610		
hard sand & shale	2655		
		<u>Total Depth</u>	

Deepened and cemented 5 $\frac{1}{2}$ " liner, 4533' to 4654'. Commenced: 4-4-47 Completed: 4-19-47

sandy lime	4629	lime	<u>Total Depth</u>	4686
------------	------	------	--------------------	------

Plugged back 5-7-48 with Lane-Wells plug set at 4364'. Light production in formation.

Certificate

I, Ben V. Kelley, Production Superintendent of The Shallow Water Refining Company, do certify that to the best of my knowledge and belief, the above is a true and correct log of the Pile Well No. 3, located C E $\frac{1}{2}$  S $\frac{1}{4}$  Section 14-20S-33", Scott County, Kansas.

Subscribed and sworn to before me, in and for the County of Finney, State of Kansas, this 10th day of February, 1955.

My Commission Expires December 10, 1958.

Notary Public