


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-171-00041-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Scott County, Sec. 27 Twp. 20S Rge. 33W (E) (W)
Location as "NE/CNW/SW" or footage from lines C SW NE
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Corn "A" Well No. 1
Office Address 780 Fourth National Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 8, 1960
Application for plugging filed September 8, 1960
Application for plugging approved September 8, 1960
Plugging commenced September 8, 1960
Plugging completed September 8, 1960
Reason for abandonment of well or producing formation No commercial quantities
of oil found.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert P. Leiker
Producing formation Depth to top Bottom Total Depth of Well 4781 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	216'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set first plug at 500 feet with 20 sacks of cement; Set second plug at 250 feet with 20 sacks of cement; Set top plug at 40 feet with 10 sacks of cement.

RCWO
10-05-60

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil of Kansas, Inc.
Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
R. L. Bacon (employee of Imperial Oil of Kansas, Inc. operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: R. L. Bacon Vice-Pres.

780 Fourth National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of October, 1960

Mona L. Lister
Notary Public.

My commission expires July 7, 1962

15-171-00041-00-00

R

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Building
Wichita 2, Kansas

Corn "A" No. 1
C SW NE Sec. 27-20-33W
Scott County, Kansas

Total Depth: 4781'

Elevation: 2944' K.B.
Production: Dry

Commenced: 8-22-60 Completed: 9-8-60

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" surface pipe at 216' with 200 sacks cement.

Figures indicate bottom of formations:

TOPS

Sand	230'	Heebner	3794 (- 850)
Sand & Shale	650'	Toronto	3807 (- 863)
Shale & Sand	1138'	Lansing	3839 (- 895)
Shale	2033'	B/Kansas City	4296 (-1352)
Anhydrite	2103'	Marmaton	4311 (-1367)
Shale	2150'	"Cherokee	4466 (-1522)
Shale & Shells	2365'	Morrow	4601 (-1657)
Shale & Lime	2615'	St. Genevieve	4651 (-1707)
Shale & Shells	2715'	St. Louis	4701 (-1757)
Shale & Lime	3775'	Total Depth	4781 (-1837)
Lime	4781'		
Total Depth	4781'		

We hereby certify the above to be a true and correct log of the above described well, according to the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By R. J. Boone
R. J. Boone, Petr. Engr.

Subscribed and sworn to before me this 16th day of September, 1960.

My Commission Expires:

July 7, 1962

Mona L. Latier, Notary Public