

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15-171-00046-00-00
WELL PLUGGING RECORD

NORTH

X			

Locate well correctly on above
Section Plat

County, Sec. 27 Twp. 20S Rge. 33 (E) W(W)
Location as "NE/CNW/SE/SW" or footage from lines C SW 1/4 SW 1/4
Lease Owner Imperial Oil of Kansas
Lease Name Corn Well No. 1
Office Address Union National Bank Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 7, 19 56
Application for plugging filed April 7, 19 56
Application for plugging approved April 7, 19 56
Plugging commenced April 8, 19 56
Plugging completed April 8, 19 56
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Boundage
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4850 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	308	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 235 feet - put in 1/3 sack hulls, plug, 25 sacks cement.

Filled hole with heavy mud to 35' of top - put in 1/3 sack ~~hulls~~ hulls, second plug, 10 sacks cement.

Cut off pipe below plow depth.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Schafer Drilling Co.
Address Box 350, Pratt, Kansas

STATE OF Kansas, COUNTY OF Pratt, ss.
Lou Guthridge (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lou Guthridge
Pratt, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 9th day of April, 19 56

My commission expires May 16, 1957

Marilyn Guthridge
Notary Public.

24-7368-S 3-53-20M

PLUGGING
FILE SEC. 27 T. 20 R. 33 W.
BOOK PAGE 52 LINE 34

APR 11 1956
STATE CORPORATION COMMISSION
WICHITA, KANSAS

15-171-000416 00-00

April 9, 1956

24-26-324

CORN #1
Drillers Log
Scott County, Kansas

0-254	Sand and Shale
254-308	Shale and Shells
308-466	Shale
466-800	Shale and Shells
800-845	Iron Pyrite (Very Hard), Mixture of Red Bed, Sand and Post Rock
845-1810	Shale, Sand and Shells
1810-1995	Shale, Shells, Red Bed
1995-2403	Shale, Red Bed and Shells
2403-2558	Shale and Salt, Iron Pyrite
2558-2685	Shale and iron Lime
2685-2775	Lime, Shale and Red Bed
2775-3160	Shale and Lime
3160-3220	Lime, Shale and Chalk
3220-4570	Lime and Shale
4570-4582	Lime
4582-4744	Lime and Shale
4744-4755	Mississippi Lime
4755-4776	Lime and Shale
4776-4850	Lime
4850	TOTAL DEPTH

I certify that the above drillers log is true and correct as taken directly from the daily drilling reports of the Corn #1

Schaper Drilling Co. by J. Guttridge
SCHAPER DRILLING CO.

State of Kansas: County of Pratt; SS

The above was subscribed and sworn to before me this 9th day of April, 1956.

Marilyn Guttridge
Notary Public

My commission expires May 16, 1959.

PLUGGING
FILE SEC 27 T 20 R 33W
BOOK PAGE 52 LINE 36