

15-171-30006-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Finney County. Sec. 24 Twp. 20S Rge. (E) 33 (W)

Location as "NE/CNW&SW4" or footage from lines. NWSE
Lease Owner Colorado Oil & Gas Corporation
Lease Name Dague Well No. 1-24
Office Address P. O. Box 158, Liberal, Kansas 67901
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-15-65 19
Application for plugging filed 11-29 19 65
Application for plugging approved 12-1 19 65
Plugging commenced 12-1 19 65
Plugging completed 12-2 19 65
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. Nichols
Producing formation None Depth to top Bottom Total Depth of Well 2716 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
None				7"	351'	None
				4-1/2"	2715'	2123'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cemented with 20 sacks TD to 2500', set plug at 2500'. Shot casing off at 2114'. Filled hole with mud. Ran 20 sacks cement plug at 600', and another 20 sack cement plug at 300'. Filled hole with mud, ran 10 sack cement plug 35' to 4' below ground level.

NOTE: Application to Plug made 11-29-65 and well log filed.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sargent's Casing Pulling Service
Address Box 506, Liberal, Kansas 67901

STATE OF Kansas, COUNTY OF Seward, ss.
L.H. Waters (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L.H. Waters
Box 158, Liberal, Kansas 67901
(Address)

SUBSCRIBED AND SWORN TO before me this 21st. day of December 19 65
William B. Claunch
Notary Public.

My commission expires 11-1-66

Orig: State Corp. Comm.
cc: A. J. Smith
(2) Wichita
Accounting
File

CONTRACTOR'S WELL LOG

OWNER:	COLORADO OIL COMPANY.
CONTRACTOR:	CHEMICAL & TECHNICAL SERVICES, INC.
WELL:	DAGUE #1-24
LOCATION:	C NW SE SEC. 24-20S-33W
	SCOTT COUNTY, KANSAS
COMMENCED:	APRIL 30, 1965
COMPLETED:	MAY 3, 1965

0	70	Clay & Sand
70	197	Sand
197	1161	Shale
1161	1506	Shale, Redbed & Lime
1506	1530	Shale, Redbed & Anhydrite Streaks
1530	2716	Shale & Lime
2716		Rotary Total Depth

Set 7" surface casing @ 351 ft. with 150 sx cement.

Set 4-1/2" production casing @ 2715 ft. with 100 sx cement.

We hereby certify that the above is a correct and accurate log of the above mentioned well, as shown on the daily drilling reports.

CHEMICAL & TECHNICAL SERVICES, INC.

BY: *R. J. McCarthy*
 Asst. Treasurer

Subscribed and sworn to before me this 11th day of May, 1965.

Carla S. Sellen
 Notary Public

My Commission Expires January 20, 1968

RECEIVED
STATE CORPORATION COMMISSION

DEC -1 1965

CONSERVATION DIVISION
Wichita, Kansas