


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Scott County, Sec. 20 Twp. 20 Rge. 33 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
C SW

Lease Owner The Maurice L. Brown Company
Lease Name R. L. Crist "E" Well No. 1
Office Address 200 Sutton Place, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed April 30 1979
Application for plugging file(verbally) April 30 1979
Application for plugging approved(verbally) April 30 1979
Plugging commenced April 30 1979
Plugging completed April 30 1979
Reason for abandonment of well or producing formation _____
No commercial quantity of oil or gas encountered.
If a producing well is abandoned, date of last production _____
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes _____

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2810'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

T.D. 2810'
Set 1st plug at 770' with 70 sacks
2nd plug at 300' with 20 sacks
3rd plug at 40' solid bridge with 10 sacks
rathole with 5 sacks.
Cemented with 50/50 posmix, 6% gel.
Plug was down at 1:30 p.m., 4-30-79.

RECEIVED
STATE CORPORATION COMMISSION

MAY 7 1979

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec. Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of May, 19 79



Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

My commission expires 8-21-82

CONTRACTOR'S WELL LOG

OPERATOR: The Maurice L. Brown Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: R. L. Crist "E" #1
 LOCATION: C SW, Section 20-20-33
 Scott County, Kansas
 SPUD DATE: April 25, 1979
 COMPLETION DATE: April 30, 1979

0	100	Clay sand
100	685	Shale
685	1445	Shale and sand
1445	2136	Shale
2136	2154	Anhydrite
2154	2645	Shale and lime
2645	2810	Lime and shale
	2810	Rotary Total Depth

Spud hole at 2:00 p.m., April 25, 1979. Drilled 370' of 12 1/4" hole. Ran 13 joints of 8-5/8" - 24# casing. Set at 369' with 150 sacks of HLC, 3% Ca.Cl., 1/4# floccel per sack followed with 150 sacks of Class H, 3% Ca.Cl. 1/4# floccel per sack. Cement did circulate. Plug was down at 11:30 p.m., April 25, 1979.

T.D. 2810'. Set 1st plug at 770' with 70 sacks, 2nd plug at 300' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Job was complete at 1:30 p.m., April 30, 1979.

SAMPLE TOPS:
 Anhydrite 2136'
 B/Anhydrite 2154'

RECEIVED
 STATE GEOLOGICAL COMMISSION

MAY - 7 1979

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the R. L. Crist "E" #1, C SW, Section 20-20-33, Scott County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 4th day of May, 1979.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 8-21-82.