


15-171-00040-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Scott County. Sec. 19 Twp. 20S Rge. 33W (E) (W)
Location as "NE/CNWxSWx" or footage from lines C NW NE
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Miller Well No. 1
Office Address 780 Fourth National Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 23, 1960
Application for plugging filed November 23, 1960
Application for plugging approved November 23, 1960
Plugging commenced November 23, 1960
Plugging completed November 23, 1960
Reason for abandonment of well or producing formation No commercial quantities of oil found.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Gilbert P. Leiker
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4850 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	311'	Not pulled

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set first plug at 300 feet with
20 sacks of cement; Set top plug
at 40 feet with 10 sacks of cement.

RECEIVED
12-19-60
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil of Kansas, Inc.
Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK ss.

R. L. Bacon (employee of owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: R. L. Bacon V-P
780 Fourth National Bldg., Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of December 19 60

My commission expires July 7, 1962

Mona L. Latier
Mona L. Latier Notary Public.

15-171-00040-00-00

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Building
Wichita 2, Kansas

Miller #1
C NW NE Sec. 19-20S-33W
Scott County, Kansas

Total Depth: 4850*

Commenced: 11-8-60 Completed: 11-23-60

Elevation: 2979' K.B.
Production: D & A

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 311' with 275 sacks cement.

Figures indicate bottom of formations:

		<u>TOPS</u>	
Shale & Sand	311'		
Shale & Shells	1400'	Winfield	2663' (/ 316)
Shale & Sand	1950'	Heebner	3850' (-871)
Shale & Shells	2425'	Toronto	3871' (-892)
Shale & Lime	4850'	Lansing	3900' (-921)
Total Depth	4850'	Base/Kansas City	4344' (-1365)
		Marmaton	4359' (-1380)
		Cherokee shale	4496' (-1517)
		Morrow shale	4674' (-1695)
		St. Genevieve	4737' (-1758)
		St. Louis	4821' (-1842)
		Rotary Total Depth	4850' (-1871)

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: W. H. Brown
Vice-President

Subscribed and sworn to before me this 9th day of December, 1960.

My Commission Expires:

July 7, 1962 STATE COMMISSION

Mona L. Lutes
Notary Public

DEC 19 1960
CONSERVATION DIVISION
Wichita, Kansas