

LEASE NAME Mark

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

3630 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 18 TWP. 20S RGE. 33W (E) or (W)

COUNTY Scott

Date Well Completed \_\_\_\_\_

Plugging Commenced 8-27-93

Plugging Completed 9-1-93

LEASE OPERATOR Lang Family Partnership

ADDRESS 4770 E. Schulman Ave. Garden City Ks. 67846

PHONE# (316) 275-2005 OPERATORS LICENSE NO. 31075

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-27-93 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.O. 4742

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1205	0
				5 1/2	4719	1569

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set  
Pump 20 sks. of cement & 1 sk. of hulls from 4697 to 4450

Pump 40 sks. of cement from 1569 to 1469

Pump 50 sks. of cement from 1240 to 1120 Pump 30 sks. of cement @ 650 to 550

Put 10 sks. of cement from 40 to 0 Cut off & cap 8 5/8 4' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lang Family Partnership

STATE OF Kansas COUNTY OF Scott

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 05 1993


CONSERVATION DIVISION  
Wichita, Kansas

(Employee of Operator) or (Operator) \_\_\_\_\_  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts  
statements, and matters herein contained and the log of the above-described well as filed the  
the same are true and correct, so help me God.

(Signature) Sherman Lang

(Address) 70 N. Farmland Rd G.C. Ks

SUBSCRIBED AND SWORN to before me this 3 day of October, 19 93



Notary Public

My Commission Expires: \_\_\_\_\_