

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-171-19047-00-00

LEASE NAME Williams

WELL NUMBER # 3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4280 Ft. from S Section Line

4280 Ft. from E Section Line

SEC. 18 TWP. 20S RGE. 33 (E) or (W)

COUNTY Scott

Date Well Completed _____

Plugging Commenced Sept 18, 1985

Plugging Completed Sept 20, 1985

LEASE OPERATOR Herman Lang Oil and Gas

ADDRESS Route 2 Garden City, Ks. 67846

PHONE# (316) 275-1953 OPERATORS LICENSE NO. 5848

Character of Well Salt Water Disposal

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? KDHE Dodge City, Ks.

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation Cedar Hills Sand Depth to Top _____ Bottom 2008 T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

See attached plugging log

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Da Mae Drilling License No. Drilling Contractor

Address 625 South Washington / P.O. Box 1164 Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Herman Lang


(Address) R R 2

SUBSCRIBED AND SWORN TO before me this 12 day of October, 19 85

My Commission Expires: Sept 30, 1988

Notary Public

STATE CORPORATION COMMISSION



OCT 15 1985

CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 08-84

Plugging Well Log

15-171-19047-00-00

Moved rotary in Sept. 18, 1985 on Williams #3 Disposal
Rigged up and ran $3\frac{1}{2}$ " drill collars to 50' stopped.
Put on $3\frac{3}{4}$ " flat bottom mill at 50' - pulled drill collars,
changed to $3\frac{1}{2}$ " flat bottom mill.

Milled out bad casing and ran mill to 980' - mill stopped
at 980'

Pulled pipe, ran $2\frac{3}{8}$ " tubing with flat bottom mill to
1,020' - mill stopped at 1,020'

Bob Flynn with NL ACME TOOL called Rick Lacy of
KDHE Dodge City, Ks. and requested plugging orders.
Plugging orders were granted with 150 sacks of cement.

Procedure to plug circulated cement to top through
 $2\frac{3}{8}$ " tubing. Pulled 20 joints, pumped full of circulated
cement again.

Pulled all but 5 joints of tubing, circulated cement
again, then filled hole with cement

Rig completed plugging well Sept 20, 1985

RECEIVED
STATE CORPORATION COMMISSION

OCT 1 1985

CONSERVATION DIVISION
Wichita, Kansas