

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-20876-00-00  
Spot: NESW Sec/Twnshp/Rge: 26-30S-18W  
1935 feet from S Section Line, 3299 feet from E Section Line  
Lease Name: EMERSON Well #: 2-A  
County: KIOWA Total Vertical Depth: 5175 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4825		WITH 2 SX CMT
SURF	8.625	512		WITH 400 SX CMT
PROD	5.5	5165	1416	WITH 250 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/23/2012 11:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: SET CIBP @ 4825' WITH 2 SX CMT. PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. PLUG AT 540' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: DANIEL BERNASCONI

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 01/23/2012 1:30 PM

KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 4825' WITH 2 SX CMT. 1ST PLUG AT 989' WITH 15 SX GEL & 50 SX CMT. HAD GOOD CIRCULATION. AFTER DISPLACEMENT, FLUID STARTED BLOWING BACK IN TRUCK. WENT TO PULL UP TO NEXT PLUG, CASING WAS STUCK. HOLE WAS FULL OF FLUID. RAN RIPPER TO 800' & COULD NOT GET CASING RIPPED. PULLED UP TO 600' & TRIED AGAIN & WAS UNSUCCESSFUL. EVENTUALLY GOT RIPPED AT 546'. CASING LEFT IN HOLE FROM 989' TO 546'. 2ND PLUG AT 544' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:


Top	Bot	Thru	Comments
4876	4884		MARMATON

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED

FEB - 3 2012

KCC DODGE CITY



RECEIVED

FEB 07 2012

KCC WICHITA

Form CP-23

