

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-001-21215-00-00
SWSENE Sec/Twp/Rge 16 - 26S - 21E
2908 feet from south section line
686 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: State of Kansas

Lease/Well# Daniels MUR26-O (22)
County Allen
Well Total Depth 695 feet

Name & _____
Address _____

Production Pipe: 2.875 Size Feet 695
Surface Casing: 6 Size Feet _____

AB oil well XXXX Gas Well _____ SWD Well/ Input Well D & A

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road Chanute, KS 66720

Company to plug at: Hour: _____ Day: _____ 18 Month: 12 2009

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: 620-431-9212

Were: Clean out and prepare well for plugging and circulate cement to surface.

Plugging Proposal Received by: Ryan M. Duling

Plugging attended by Agent: All _____ Part _____
TECHNICIAN
None XXXX

Operations Completed: Hour: _____ Day: _____ 18 Month: 12 2009

Actual Plugging Report: Dug down beside the 2.875" with a backhoe approximately 4' and found the casing surrounded by cement. Ran 1" pipe down the inside of 2.875" casing to 690'. Washed 1" pipe down the inside of the 2.875" casing to 695'. Circulated cement through the 1" pipe inside the 2.875" casing from 695' to surface. Pulled the 1" pipe. Topped the well off with cement. A total of 35 sacks of portland cement was used to plug this well. The well was cut off below grade and the site was restored.

Remarks: Contract #12391 Control #20100001-026
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed:

[Signature]
TECHNICIAN

RECEIVED
NAD 83 JAN 16 2011
95.10875649 87.7839678
KCC WICHITA