

To: STATE CORPORATION COMMISSION
 Wichita State Office Bldg. - PLUGGING SECTION
 130 S. Market, Room 2078
 Wichita, Kansas 67202

API NUMBER 15-001-21041-00-01
 SWNESE _____ Sec/Twp/Rge 16 - 26S - 21E
 _____ 4040 feet from south section line
 _____ 897 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Daniels MUR36-O (W-2)

Operator: State of Kansas

County Allen

Name & _____

Well Total Depth 550 feet

Address _____

Production Pipe: 6.25" Size Feet 550

AB oil well _____ Gas Well _____ SWD Well/ Input Well EDR XXXX D & A _____

Surface Casing: _____ Size Feet _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road Chanute, KS 66720

Company to plug at: Hour: _____ Day: _____ 6 Month: 11 2009

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: 620-431-9212

Were: Clean out and prepare well for plugging and circulate cement to surface.

Plugging Proposal Received by: Ryan M. Duling

Plugging attended by Agent: All _____ Part _____ TECHNICIAN _____
 _____ None XXXX

Operations Completed: Hour: _____ Day: _____ 6 Month: 11 2009

Actual Plugging Report: Excavated around 6.25" casing approximately 4' below surface. Split casing approximately 4'. The 2" casing is cemented in approximately 1'. Mud is present below the cement. Washed 1" pipe with reamer down to 550'. Pulled 1" pipe and reamer. Perforated well at 500' and 200'. Ran 1" pipe down 2" casing to 550'. Circulated cement through 1" down 2" casing to surface. Pulled 50' of 1" pipe and circulated at 500' to surface. Pulled 300' of 1" pipe and circulated cement at 200' to surface. Pulled the rest of 1" pipe and topped the well off. A total of 21 sacks of portland cement was used to plug this well. The well was cut off below grade and the location was restored.

Remarks: Contract #12391 Control #20100001-036 GPS 4-14-09 NAD 83

(If additional description is necessary, use BACK of this form.)

-95.10949804 37.78708164

I did not observe this plugging.

Signed: _____

RECEIVED
83 JAN 24 2011
KCC WICHITA

 TECHNICIAN