

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-001-22 251-00-01
SWSENE Sec/Twp/Rge 16-26S-21E
2692 feet from south section line
908 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Daniels MUR39-I (W-43)

County Allen

Operator: State of Kansas

Well Total Depth 695 feet

Name &

Production Pipe: 2.875 Size Feet 695

Address

Surface Casing: 7 Size Feet

AB oil well Gas Well SWD Well/ Input Well EOR XXXX D & A

Other well as hereinafter indicated:

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road Chanute, KS 66720

Company to plug at: Hour: Day: 18 Month: 12 2009

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: 620-431-9212

Were: Clean out and prepare well for plugging and circulate cement to surface.

Plugging Proposal Received by: Ryan M. Duling

Plugging attended by Agent: All Part XXXX None

Operations Completed: Hour: Day: 18 Month: 12 2009

Actual Plugging Report: Dug down beside the 2.875" casing with a backhoe approximately 4' and

found the casing surrounded by cement. Ran 1" pipe inside the 2.875" casing to 575'. Washed 1" pipe

down the inside of the 2.875" casing from 575' to 695'. Circulated cement through the 1" pipe inside the

2.875" casing from 695' to surface. Pulled 300' of 1" pipe. Circulated cement through the 1" pipe inside

the 2.875" casing from 400' to surface. Pulled the rest of the 1" pipe. A total of 28 sacks of portland

cement was used to plug this well. The well was cut off below surface and the site was restored.

Remarks: Contract #12391 Control #20100001-039 GPS 4-15-09 NAD 83

(If additional description is necessary, use BACK of this form.)

I did observe this plugging.

Signed:

Ryan M. Duling
KCC WICHITA
TECHNICIAN

RECEIVED
JAN 24 2011