

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-001-20998-00-00
NWSENE Sec/Twp/Rge 16-26S-21E
3819 feet from south section line
1115 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Daniels MUR42-0 (3)

County Allen

Operator: State of Kansas

Well Total Depth 695 feet

Name &

Production Pipe: 2.875 Size Feet 695

Address

Surface Casing: Size Feet

AB oil well XXXX Gas Well

SWD Well/ Input Well D & A

Other well as hereinafter indicated:

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road Chanute, KS 66720

Company to plug at: Hour: Day: 11 Month: 12 2009

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: 620-431-9212

Were: Clean out and prepare well for plugging and circulate cement to surface.

Plugging Proposal Received by: Ryan M. Duling

TECHNICIAN
None

Plugging attended by Agent: All XXXX Part

Operations Completed: Hour: Day: 11 Month: 12 2009

Actual Plugging Report: Dug down beside the 2.875" casing with a backhoe approximately 4' and

found the casing surrounded by cement. Ran 1" down the inside of the 2.875" casing to 645'. Washed 1"

down the inside of the 2.875" casing to 695'. Circulated cement through the 1" pipe inside the 2.875"

casing from 695' to surface. Pulled 350' of 1" pipe. Circulated cement through the 1" pipe inside the

2.875" casing from 350' to surface. Pulled the rest of the 1" pipe. Topped well off with cement. A total of

29 sacks of portland cement was used to plug this well. The well was cut off below surface and the site

was restored.

-95.11025048 87.78647800 RECEIVED

Remarks: Contract #12391 Control #20100001-042 GPS 4-15-09 NAD 83 JAN 24 2011
(If additional description is necessary, use BACK of this form.)

I did observe this plugging.

Signed:

Ryan M. Duling
TECHNICIAN

KCC WICHITA