

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-001-21295-00-00
SWNE NE Sec/Twp/Rge 16-26S-21E
4254 feet from south section line
1112 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Daniels MUR43-O (10)

County Allen

Operator: State of Kansas

Well Total Depth 620 feet

Name & _____

Production Pipe: 2.875 Size Feet _____

Address _____

Surface Casing: _____ Size Feet _____

AB oil well XXXX Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road Chanute, KS 66720

Company to plug at: Hour: _____ Day: 11 Month: 12 2009

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: 620-431-9212

Were: Clean out and prepare well for plugging and circulate cement to surface.

Plugging Proposal Received by: Ryan M. Duling

Plugging attended by Agent: All _____ Part XXXX None _____
TECHNICIAN

Operations Completed: Hour: _____ Day: 11 Month: 12 2009

Actual Plugging Report: Dug down beside the 2.875" casing with a backhoe approximately 4' and

found the casing surrounded by cement. Ran 1" pipe down the inside of the 2.875" casing to 620'.

Circulated cement through the 1" pipe inside the 2.875" casing from 620' to surface. Pulled 300' of 1" pipe.

Circulated cement through the 1" pipe inside the 2.875" casing from 300' to surface. Pulled the rest of the

1" pipe. Topped well off with cement. A total of 26 sacks of portland cement was used to plug this well.

The well was cut off below surface and the site was restored.

Remarks: Contract #12391 Control #20100001-043 GPS 4-15-09 NAD 83
(If additional description is necessary, use BACK of this form.)

RECEIVED
37.78761365
JAN 24 2011

I did observe this plugging.

Signed: Ryan M. Duling
TECHNICIAN

KCC WICHITA