

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-001-21034-00-00  
~~SWNE~~ NE Sec/Twp/Rge 16-26S-21E  
3396 feet from south section line  
1534 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101  
Operator: State of Kansas

Lease/Well# Daniels MUR53-O (17)  
County Allen  
Well Total Depth 665 feet

Name & \_\_\_\_\_  
Address \_\_\_\_\_

Production Pipe: 2.875 Size Feet 665  
Surface Casing: \_\_\_\_\_ Size Feet \_\_\_\_\_

AB oil well XXXX Gas Well \_\_\_\_\_ SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road Chanute, KS 66720

Company to plug at: Hour: \_\_\_\_\_ Day: 13 Month: 11 2009

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: 620-431-9212

Were: Clean out and prepare well for plugging and circulate cement to surface.

Plugging Proposal Received by: Ryan M. Duling

TECHNICIAN

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXX

Operations Completed: Hour: \_\_\_\_\_ Day: 13 Month: 11 2009

Actual Plugging Report: Dug down beside the 2.875" casing with a backhoe approximatley 4' and found casing surrounded by cement. Pulled 50' of 1" with packer out of the 2.875" casing. Ran 1" pipe down 2.875" casing to 660'. Washed 1" pipe down to 665'. Circulated cement through 1" pipe from 665' to surface. Pulled 325' of 1" pipe. Circulated cement from 300' to surface. Pulled the remaining 300' of 1" pipe and topped off the well with cement. A total of 25 sacks of portland cement was used to plug this well. The well was cut off below grade and the location was restored.

-95.11169812 37.7853263 RECEIVED

Remarks: Contract #12391 Control#20100001-053 GPS 4-15-09 NAD 83 JAN 24 2011  
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed:

Ryan M. Duling  
TECHNICIAN

KCC WICHITA