

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21241-00-01
Spot: SWSWNW Sec/Twnshp/Rge: 4-10S-21W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease Name: RUDMAN Well #: 1
County: GRAHAM Total Vertical Depth: 3886 feet

Operator License No.: 8942
Op Name: V & F OIL COMPANY, A GENERAL PAR
Address: 512 W 31ST ST
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3400		
SURF	8.625	240		100 SX
PROD	5.5	3886		300 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 02/01/2012 9:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: WILLIAM VAN LOENEN Company: V & F OIL CO. Phone: (785) 625-3090

Proposed Plugging Method: Ordered-350sxs 60/40 poz mix 4% gel; 400lbs hulls
PBTD-2650
Milled 4-7/8" hole to 2600' & went out of CSG.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/01/2012 3:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Log Tech RIH & stacked out with perforating gun @ 2150' perfed holes @ 2150-1785-1060 ft. Poe Well Service RIH with tubing to 2131' Allied rigged to tubing & mixed & pumped 105 sxs cement with 200 # hulls mixed in.
Pulled tubing to 1065' Allied rigged to tubing & pumped 120 sxs with 200 # hulls mixed to circulate cement to pit area.
Pulled tubing Allied rigged to 5-1/2" CSG with a swedge & pumped 5 sxs to pressure with 300# PSI & 200# SIP.
Cut hole with torch in 8-5/8" CSG found CSG to be full of cement.

Perfs:

Top	Bot	Thru	Comments
3886			

RECEIVED
FEB 07 2012
KCC WICHITA

Remarks: ALLIED OIL & GAS LLC. TICKET # 56951

Plugged through: TBG

District: 04

Signed *Pat Staab*
(TECHNICIAN)

FEB 02 2012

Form CP-2/3

2/10/12