

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-25650-00-00  
Spot: NENENESE Sec/Twnshp/Rge: 1-17S-15W  
2520 feet from S Section Line, 25 feet from E Section Line  
Lease Name: SATTERFIELD ET AL Well #: 1-1  
County: BARTON Total Vertical Depth: 3600 feet

Operator License No.: 3882  
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN  
Address: 1515 WYNKOOP, STE 700  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
STRL	8.625	439		200 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/31/2012 2:00 AM  
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.  
Proposal Revd. from: RANDY Company: VAL ENERGY, INC. Phone: \_\_\_\_\_

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS Witness Type: NONE  
Date/Time Plugging Completed: 01/31/2012 2:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report: Perfs:  
1st plug @3464 w/25 sx  
2nd plug @1000 w/25 sx  
3rd plug @520 w/100 sx  
4th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

Remarks: QUALITY OIL WELL CEMENTING  
Plugged through: DP

RECEIVED  
FEB 07 2012  
KCC WICHITA

District: 04 Signed CM (TECHNICIAN) CM

FEB 03 2012

✓ 2/10/12