

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-06770-00-00
Spot: E2SEW Sec/Twnshp/Rge: 30-16S-11W
3300 feet from S Section Line, 2970 feet from E Section Line
Lease Name: OESER A TWIN Well #: 1
County: BARTON Total Vertical Depth: 3245 feet

Operator License No.: 4871
Op Name: HITSCHMANN, CURTIS LEE DBA CURT
Address: PO 8
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	400		
PROD	5.5	3245		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/22/2011 12:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: D S & W WELL SERVICING, INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered 450 sx 60/40 pos 4% gel, #600 hulls

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/18/2012 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Junk in hole @1663'. Could not get through bridge.
Ran tubing to 1663'. Tied onto tubing and pumped 60 sx cmt.
Pulled tubing to 1000'. Pumped 50 sx cement.
Pulled tubing to 500'. Pumped 120 sx cement. Circulated out of surface pipe and casing.
POOH. Tied to casing and pumped 12 sx cement. SIP 300

Perfs:

Top	Bot	Thru	Comments
3112	3128		G
3062	3066		B
3044	3048		A
3036	3040		A
2936	2941		TORONTO

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

RECEIVED
FEB 07 2012
KCC WICHITA

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

FEB 03 2012

✓ 2/10/12