

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-04194-00-00  
Spot: SWNWSE Sec/Twnshp/Rge: 12-18S-11W  
1650 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: HERTACH Well #: 9  
County: BARTON Total Vertical Depth: 3295 feet

Operator License No.: 31561  
Op Name: HOFFMAN, CHRIS DBA C & K OIL COM  
Address: 410 B ST PO BOX 531  
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	260		175 SX
PROD	5.5	3291		50 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/18/2012 12:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: CHRIS HOFFMAN Company: C & K OIL Phone: (620) 786-8744

Proposed Plugging Method: Ordered 300 sx 60/40 4 % gel cement, 500# hulls

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/19/2012 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off Perfs and dump bailed 5sx cmt.  
Cut casing at 1500'. Pulled up 10' and pumped 125 sx cmt, 100# hulls.  
Pulled casing to 600'. Pumped 50 sx cmt, 100# hulls.  
Pulled casing to 260'. Circulated cmt w/90 sx.  
Pulled casing out. Hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3291	3295		ARBUCKLE

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

RECEIVED  
FEB 07 2012  
KCC WICHITA

District: 04

Signed

*Bruce Rodie*

(TECHNICIAN)

CM

Form CP-2/3

FEB 06 2012

✓ 2/10/12