

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21441-00-00
Spot: SWNESW Sec/Twnshp/Rge: 18-29S-18W
1461 feet from S Section Line, 3790 feet from E Section Line
Lease Name: GREY-UNRUH Well #: 18-1
County: KIOWA Total Vertical Depth: 5104 feet

Operator License No.: 3344
Op Name: MAGNUM OIL & GAS
Address: 8520 25TH AVE
GREENSBURG, KS 67054

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4000		WITH 2 SX CMT
SURF	8.625	350		WITH 200 SX CMT
PROD	4.5	4578	2239	WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/01/2012 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMES GREY Company: MAGNUM OIL & GAS Phone: (620) 546-5767

Proposed Plugging Method: PLUG AT 1250' WITH 15 SX GEL & 50 SX CMT. PLUG AT 500' WITH 50 SX CMT. PLUG AT 380' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/01/2012 11:50 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CIBP @ 4000' WITH 2 SX CMT. 1ST PLUG AT 1252' WITH 15 SX GEL & 50 SX CMT.
2ND PLUG AT 610' WITH 50 SX CMT. 3RD PLUG AT 396' WITH 50 SX CMT. 4TH
PLUG AT 38' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4436	4442		
4412	4415		

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

RECEIVED

FEB 08 2012

KCC WICHITA

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
FEB - 3 2012
KCC DODGE CITY

2/10/12