

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21080-00-01
Spot: SWNW Sec/Twnshp/Rge: 14-29S-18W
3338 feet from S Section Line, 4482 feet from E Section Line
Lease Name: UNRUH B Well #: 3
County: KIOWA Total Vertical Depth: 5010 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4110		
CIBP		4850		
SURF	8.625	548		WITH 250 SX CMT
PROD	4.5	5009	0	WITH 250 SX CMT

Well Type: SWD UIC Docket No: D24010.0 Date/Time to Plug: 01/04/2012 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: SHANE PELTON Company: HERMAN L. LOEB Phone: (719) 340-8987

Proposed Plugging Method: SET CIBP @ 4110' WITH 2 SX CMT. PERFORATE CASING AT 1175' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: PARTIAL
Date/Time Plugging Completed: 01/10/2012 11:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CIBP SET @ 4850'. 1/14/12: SET CIBP @ 4110'. PERFORATED AT 1175'. PUMPED 400 SX CMT WITH GOOD CIRCULATION BUT NO CMT TO SURFACE. DISPLACED WITH 2 1/2 BBL WATER THEN SHUT DOWN. 1/5/12: TAGGED CMT INSIDE THE PRODUCTION/SURFACE CASING ANNULUS AT 70'. TAGGED CMT INSIDE THE 4 1/2" CASING AT 150'. 1/10/12: FILLED VOIDS WITH GRAVEL & TOPPED OFF WITH 5 SX CMT EACH.

Perfs:

Top	Bot	Thru	Comments
4388			
4166			

Remarks: USED 60/40 POZMIX 4% GEL & 100# HULLS BY ALLIED.

Plugged through: CSG

RECEIVED

FEB 08 2012

KCC WICHITA

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED

FEB - 3 2012

KCC DODGE CITY

Form CP-2/3

✓ cc to WC 2/09/12

✓ 2/10/12