

State of Kansas



15-077-20005-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill, filed  
February 20, 1967.

Dear Sir:

Mr. Don Beauchamp of Walters Drilling Company has this date requested permission to plug the following described well:

Mr. Beauchamp guarantees payment of the plugging fee.

Operator's full Name: Walters Drilling Company

Complete Address: 400 Insurance Bldg., Wichita, Kansas

Lease Name: Hostetler Well No. # 1

Location: SE SW SW Sec. 31 Twp. 31 Rge. 7 (E)(W) W

County Harper Total Depth 4759' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Beauchamp was instructed to plug the well as follows:

214' of 8 5/8" surface pipe, cement circulated with 175 sacks. Fill hole with drilling mud to 200', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Audie Elving  
Conservation Division Agent