



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAR 2 1964  
03-12-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. T. R. Sullivan of Sierra Petroleum Co., Inc has this date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Sierra Petroleum Co., Inc.

Complete Address: 1015 Wichita Plaza, Wichita, Kansas

Lease Name: Spicer Well No. # 1

Location: C SW NW Sec. 36 Twp. 33 Rge. 10 (E) (W) W

County Barber Total Depth 4625 Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Sullivan was instructed to plug the well as follows:

207' of 8 5/8" surface pipe, cemented with 150 sacks. Fill hole with drilling mud to 200'; 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 5 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent