



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

June 29, 1965.

Dear Sir:

Mr. Art Lamb of Lamb Caseing Pulling Co. has this date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: Melland Drilling Co

Complete Address: 901 N. Main McPherson Kansas.

Lease Name: Nelson Well No. #2

Location: W/2 SE-SW Sec. 22 Twp. 16 Rge. 3 (E) (W) #

County Saline Total Depth 3347' Oil Well #

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lamb was instructed to plug the well as follows:

3332 ft. of 5 1/2" long string sanded to 3300'. 5 sacks cement  
340 ft. of 8 5/8" surface pipe circulated with cement.  
Hole filled to 300' with mud, 10' rock bridge & 20 sacks  
cement. Hole filled to 40' with mud, 10' rock bridge & 10  
sacks cement to base of cellar.

Very truly yours,

07-01-1965

Hermon J. Auster  
 Conservation Division Agent