



15-169-20046-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

August 4, 1970

RECEIVED
STATE CORPORATION COMMISSION
AUG 5 1970
CONSERVATION DIVISION
Wichita, Kansas
08-05-1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock,
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Pat Plouffe of Blackstone Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Plouffe guarantees payment of the plugging fee.

Operator's full Name: Western Diversified Industries

Complete Address: 806 Beacon Bldg., Tulsa, Oklahoma

Lease Name: Lovett Well No. 1

Location: C SE SW Sec. 16 Twp. 16 Rge. 3 (W) X

County: Saline Total Depth 3549' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Plouffe was instructed to plug the well as follows:

Fill hole with mud to 325'. Push plug and 1/4 sack hulls to 325' and
cement hole with 25 sacks cement through drill pipe. Fill hole with
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10
sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

William D. Loren
Conservation Division Agent