



15-1109-20052-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

July 15, 1971

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1971
CONSERVATION DIVISION
Wichita, Kansas
07-22-1971

Dear Sir:

Mr. Pat Flouffe of Blackstone Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Flouffe guarantees payment of the plugging fee.

Operator's full Name: Stiles-Godsey Engineering, Inc.

Complete Address: Box 4449, Tulsa, Oklahoma

Lease Name: Herbert Johnson Well No. 1

Location: SE SE SW Sec. 9 Twp. 16 Rge. 3 (E)(W) X

County: Saline Total Depth 3603 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Flouffe was instructed to plug the well as follows:

Fill hole with mud to 250'. Push plug and 1/2 sack hulls to 250' and
cement hole with 25 sacks cement through drill pipe. Fill hole with
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10
sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

Conservation Division Agent