

15-077-20001-0000

Form CP-3
Rev. 6-26-62

W
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
FEB 2 1967
2-3-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Walters Drilling Company

Complete Address: 400 Insurance Bldg., Wichita, Kansas

Lease Name Bottorff *Bottorff* Well No. # 1

Location SW SW SE Sec. 31 Twp. 31 Rge. 7 (E) (W) W

County Harper Total Depth 4774'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Walters Drilling Company

Address: 400 Insurance Bldg., Wichita, Kansas License No.

Operation Completed: Hour 4:00PM Day 2nd Month Feb. Year 1967

The Above well was plugged as follows:

216' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole was
filled with drilling mud to 200', 1st cementing plug bridged with dry
cement and hulls on fluid at 200', and cemented with 25 sacks. Hole was fill-
ed with drilling mud to 40', 2nd cementing plug, bridged with 1/2 sack of hulls
on fluid at 40', and cemented with 10 sacks to the base of the cellar.
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audrie Elving
Well Plugging Supervisor

DATE 2/3/67
INV. NO. 4916-4