

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-007-206910 (1 of this well)

Operator's Full Name Texas Oil & Gas Corp.

Complete Address 200 W. Douglas, Suite 300, Wichita, Ks. 67202

Lease Name Frisbie Well No. 1

Location SW NE SW Sec. 25 Twp. 33S Rge. 10 (E) (W) X

County Barber Total Depth 4615

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Clarke Corp.

Address 107 W. Fowler, Medicine, Lodge, Ks. 67104 License No. 583

Operation Completed: Hour 1 Pm. Day 19 Month 6 Year 1979

The above well was plugged as follows:

214' 8 5/8" casing w/185 sax cement. 4 1/2" casing set at 4514' w/150
sax cement. Plug back to 4400'-Build bridge at 2550'-Preforated at 2520'
Sand back to 2500'-Top sand w/4 sax mixed cement w/ dump bailer. Pull
2430' 4 1/2" casing. Build bridge at 210' & dump 3 yard ready mix cement
in 8 5/8" casing to top of casing by Harper Ready Mix.

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1979

I hereby certify that the above well was plugged as herein stated, Kansas

CONSERVATION DIVISION
WELL PLUGGING SUPERVISOR
Signed: Dee Dees
Well Plugging Supervisor

INVOICED
DATE 6-21-79
INV. NO. 9879-W