

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 34579
Name: COBALT ENERGY LLC
Address 1: 115 S BELMONT #12
Address 2: PO BOX 8037
City: WICHITA State: KS Zip: 67208 + _____
Contact Person: NICHOLAS HESS
Phone: (316) 201-4101
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 051-26258-00-00
Spot Description: _____
W2 NE SE SE Sec. 11 Twp. 12 S. R. 19 East West
990 Feet from North / South Line of Section
335 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: ELLIS
Lease Name: JOY ESTATE "A" Well #: 1-11
Date Well Completed: 2/5/12
The plugging proposal was approved on: 2/1/12 (Date)
by: MARVIN MILLS (KCC District Agent's Name)
Plugging Commenced: 2/4/12
Plugging Completed: 2/5/12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		SURFACE	8 5/8	244	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged well with 245 sacks of 60/40 Poz, 4% gel, 1/4# flo-seal per sack, 1st plug @ 3780' with 25 sacks, 2nd plug @ 1520' with 25 sacks, 3rd plug @ 780' with 100 sacks, 4th plug @ 294' with 40 sacks, 5th plug @ 40' to surface with 10 sacks, 30 sacks for rat hole, 15 sacks for mouse hole, by Allied (Ticket #056955), plug was down @ 7:45 am on 2/5/2012.

Plugging Contractor License #: 33350 Name: SOUTHWIND DRILLING, INC
Address 1: 8 NORTH MAIN Address 2: PO BOX 276
City: ELLINWOOD State: KANSAS Zip: 67526
Phone: (620) 564-3800

RECEIVED
FEB 08 2012

Name of Party Responsible for Plugging Fees: COBALT ENERGY LLC
State of KANSAS County, BARTON, ss.

KCC WICHITA

JILL WAHLMEIER Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Jill Wahlmeier



Southwind Drilling, Inc.
 Plugging Orders & Reports

Lease: Joy Estate "A" # 1-11

Plugging Received from KCC Representative:

Name: Marrin Mills Date: 2-1-12 Time: 2:30 PM

1 st plug @ <u>3780</u> feet, <u>25</u> sacks	Stands <u>60</u>
2 nd plug @ <u>1520</u> feet, <u>25</u> sacks	Stands <u>24</u>
3 rd plug @ <u>780</u> feet, <u>100</u> sacks	Stands <u>12.5</u>
4 th plug @ <u>294</u> feet, <u>40</u> sacks	Stands <u>4.5</u>
5 th plug @ <u>40</u> feet, <u>10</u> sacks	Stands <u>.5</u>

Mousehole: 15 sacks

Rathole: 30 sacks

Total Cement Used: 245 sacks

Type of cement: 60% Poz 4% Gel 1/4# FS

Plug Down @ 7:45 AM 2-05-12

Call KCC When Completed:

Name: Rich Williams Date: 2-6-12 Time: 9:00 AM

RECEIVED
 FEB 08 2012
 KCC WICHITA