

Notice: Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 4824  
Name: Pioneer Natural Resources USA, Inc.  
Address 1: 5205 North O'Conner Blvd  
Address 2: \_\_\_\_\_  
City: Irving State: TX Zip: 75039 + 3707  
Contact Person: Virginia Tijerina  
Phone: (972) 444-9001  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Chase Depth to Top: 2082 Bottom: 2148 T.D. 2180  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 15-129-20335-00-00  
Spot Description: \_\_\_\_\_  
NW NW SW SE Sec. 22 Twp. 33 S. R. 41  East  West  
1250 1268 Feet from  North /  South Line of Section  
2540 2571 Feet from  East /  West Line of Section  
GPS KCC  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Morton  
Lease Name: MOORE Well #: 1  
Date Well Completed: 12/30/1977  
The plugging proposal was approved on: 1/20/12 (Date)  
by: Richard Lacy (KCC District Agent's Name)  
Plugging Commenced: 1/20/2012  
Plugging Completed: 1/25/2012

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Chase		Surface	8 5/8"	409'	NONE
		Production	4 1/2"	2179'	994' - ( 23 jts )

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1 1/2" tbg stuck ( EOT @ 2133' ) . Freepoint tbg @ 1760' . Cut tbg @ 1740' , pulled 20' out & stuck again. Cut tbg again @ 1600' , POH w/ 52 jts 1 1/2" tbg . PU 2 3/8" tbg & tag fill @ 1568' . RU cement trks & spot 35 sks Class "C" cement up to 1051' . POH w/ tbg . Install 4 1/2" pull sub . Cut & pull 4 1/2" csg from 994' ( 23 jts ) . TIH w/ tbg & spot 125 sks Class "C" cement . POH & WOC . Tag TOC @ 506' . Spot additional 100 sks Class "C" cement . POH & WOC . Tag TOC @ 184' . Top out 64' - 4' w/ 20 sks cement.

Plugging Contractor License #: 33338 Name: Orr Enterprises, Inc.  
Address 1: P. O. Box 1706 Address 2: \_\_\_\_\_  
City: Duncan State: OK Zip: 73534 + 1706  
Phone: (580) 467-0258  
Name of Party Responsible for Plugging Fees: Pioneer Natural Resources USA, Inc.  
State of Texas County, Dallas , ss.  
Virginia Tijerina  Employee of Operator or  Operator on above-described well.  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Virginia Tijerina

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
FEB 13 2012  
KCC WICHITA