

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 4824 Name: Pioneer Natural Resources USA, Inc. Address 1: 5205 North O'Conner Blvd Address 2: City: Irving State: TX Zip: 75039 + 3707 Contact Person: Virginia Tijerina Phone: (972) 444-9001 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (if needed attach another sheet) Krider/Winfield Depth to Top: 2512' Bottom: 2590' T.D. 2740 Towanda Depth to Top: 2630' Bottom: 2642' T.D. 2740 Ft. Riley Depth to Top: 2672' Bottom: 2690' T.D. 2740

API No. 15 - 15-075-20008-00-00 Spot Description: SE SE NW SE Sec. 4 Twp. 26 S. R. 39 East West 1,324 Feet from North South Line of Section 1,321 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Hamilton Lease Name: O. RECTOR Well #: 1 Date Well Completed: 5/06/1968 The plugging proposal was approved on: 1/25/12 (Date) by: Daniel Bernasconi (KCC District Agent's Name) Plugging Commenced: 1/26/2012 Plugging Completed: 1/27/2012

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Formation, Content, Casing, Size, Setting Depth, Pulled Out. Rows include Krider, Winfield, Towanda, Ft. Riley.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RU sandline & tag fill @ 2430'. PU 2 3/8" tbg, TIH@ 2376'. RU cement trks & spot 30 sks Class "C" cement up to 2200'. Pull up hole w/ tbg @ 1520', mix & spot 100 sks Class "C" cement w/ 100 lbs cotton seed hulls to cover csg leak. POH w/ tbg. Tag TOC @ 1502', load & test casing @ 500 psi. RU wireline trk & perf squeeze holes @ 745'. RU down casing, breakdown & est circulation to surface, mix & pump 240 sks cement & leave full to surface.

Plugging Contractor License #: 33338 Name: Orr Enterprises, Inc. Address 1: P. O. Box 1706 Address 2: City: Duncan State: OK Zip: 73534 + 1706 Phone: (580) 467-0258 Name of Party Responsible for Plugging Fees: Pioneer Natural Resources USA, Inc. State of Texas County, Dallas, ss. Virginia Tijerina (Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Virginia Tijerina

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED FEB 13 2012 KCC WICHITA