

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 9228
Name: Marlin Oil Corporation
Address 1: P.O. Box 14630
Address 2: _____
City: Oklahoma City State: OK Zip: 73113
Contact Person: W.R. (Dick) Lynn
Phone: (405) 478-1900
Type of Well: (Check one) ☐ Oil Well ☒ Gas Well ☐ OG ☐ D&A ☐ Cathodic
☐ Water Supply Well ☐ Other: _____ ☐ SWD Permit #: _____
☐ ENHR Permit #: _____ ☐ Gas Storage Permit #: _____
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No
Producing Formation(s): List All (If needed attach another sheet)
Atoka Depth to Top: 5632 Bottom: 5642 T.D. 6650
Morrow Depth to Top: 5807 Bottom: 5811 T.D. 6650

Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 119-20955-00-01
Spot Description: _____
_____SE SW Sec. 33 Twp. 33 S. R. 30 ☐ East ☒ West
720 Feet from ☐ North ☒ South Line of Section
1980 Feet from ☐ East ☒ West Line of Section
Footages Calculated from Nearest Outside Section Corner:
☐ NE ☐ NW ☐ SE ☒ SW
County: Meade
Lease Name: Warren Well #: 1
Date Well Completed: 2/7/96
The plugging proposal was approved on: 1-13-12 (Date)
by: Richard Lacey (KCC District Agent's Name)
Plugging Commenced: 1-19-12
Plugging Completed: 1-19-12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
<u>Atoka 5632' (10')</u>	<u>gas & oil</u>				
<u>Morrow 5807 (4')</u>	<u>gas</u>	<u>Surface</u>	<u>8 5/8"</u>	<u>1535'</u>	<u>-0-</u>
		<u>Production</u>	<u>4 1/2"</u>	<u>6647'</u>	<u>2535'</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP set @ 5596' w/ 25 sks c.t. on top & hole loaded w/ mud. Shot & pulled 4 1/2' @ 2535' placed plugs as follows: 50 sks c.t. 1560'-1395', 40 sks c.t. 600'-465' 10 sks c.t. 40'-0'. With mud spacing each plug. Cut & Cap 8 5/8 4' below GL.

Plugging Contractor License #: 32833 Name: Sargent & Lillard Casing Pulling Inc.
Address 1: P.O. Box 1450 Address 2: _____
City: Woodward OK State: OK Zip: 73802 1450
Phone: (580) 254-1881
Name of Party Responsible for Plugging Fees: MARLIN OIL CORP.
State of Oklahoma County: Oklahoma, ss. _____
W.R. Lynn ☒ Employee of Operator or ☐ Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: W.R. Lynn

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
FEB 13 2012
KCC WICHITA