

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 9228  
Name: Marlin Oil Corporation  
Address 1: P.O. Box 14630  
Address 2: \_\_\_\_\_  
City: Oklahoma City State: OK Zip: 73113 + \_\_\_\_\_  
Contact Person: W.R. (Dick) Lynn  
Phone: (405) 478-1900  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Morrow Depth to Top: 5844 Bottom: 5846 T.D. 6700  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15- 119-21041-00-00  
Spot Description: 150' N of E/2 of Sec.  
S2-S2-S2 E/2 Sec. 33 Twp. 33 S. R. 30  East  West  
2490-2492 Feet from  North  South Line of Section  
1320-1359 Feet from  East  West Line of Section  
GPS-KCC  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Meade  
Lease Name: Colton Well #: 1  
Date Well Completed: 7-6-01  
The plugging proposal was approved on: 1-13-12 (Date)  
by: Richard Lacey (KCC District Agent's Name)  
Plugging Commenced: 1-25-12  
Plugging Completed: 1-25-12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
<u>Morrow</u>	<u>gas</u>	-			
		<u>Surface</u>	<u>8 5/8"</u>	<u>1536'</u>	<u>-0-</u>
		<u>Production</u>	<u>4 1/2"</u>	<u>6686'</u>	<u>2545'</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP set @ 5746' w/25sk c-t on top + hole loaded w/mud. Shot + pulled 4 1/2 @ 2545'  
Placed plugs as follows: 50 sks cut. 1560'-1395', 40 sks cut. 600-465', 10 sks cut. 40'-0'.  
With mud spacing each plug. Cut + Cap 8 5/8 4' below GL.

Plugging Contractor License #: 32833 Name: Sargent + Lillard Casing Pulling Inc  
Address 1: P.O. Box 1450 Address 2: \_\_\_\_\_  
City: Woodward State: OK Zip: 73802 + 1450  
Phone: (580) 254-1881  
Name of Party Responsible for Plugging Fees: MARLIN OIL CORP.  
State of Oklahoma County: Oklahoma, ss.  
W.R. Lynn  Employee of Operator or  Operator on above-described well.  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: W.R. Lynn

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

FEB 13 2012

KCC WICHITA