

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4 March 2009

Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 6039 Name: L.D. Drilling Inc Address 1: 7 SW 26th Ave City: Great Bend State: KS Zip: 67530 Type of Well: Oil Well Water Supply Well Other: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (if needed attach another sheet)

API No. 15 - 009-24886-00-00 Spot Description: N2 SW NW NE Sec. 32 Twp. 16 S. R. 13 East West 790 Feet from North South Line of Section 2,310 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Barton Lease Name: Mater Well #: 1 Date Well Completed: The plugging proposal was approved on: (Date) by: Bruce Rodey (KCC District Agent's Name) Plugging Commenced: 1/2/12 Plugging Completed: 1/4/12

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Casing, Size, Setting Depth, Pulled Out). Includes data for 8-5/8" and 4-1/2" casing.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

TD @ 3430', sanded bottom off. Checked hole, sand @ 3100'. Dumped 4sx cement. Pulled 523' of 4-1/2. Casing parted 2' below collar. Perforated casing @ 875' & 1600'. Pumped 100sx 60/40poz 4%gel 200# hulls. Pulled up to 875', pumped 40sx 100# hulls. Pulled up to 500', pumped 190sx 100# hulls. Cement circulated to surface. Plugging complete.

Plugging Contractor License #: 31529 Name: Mike's Testing & Salvage, Inc. Address 1: P.O. Box 467 Address 2: City: Chase State: Kansas Zip: 67524 Phone: (620) 938-2943 Name of Party Responsible for Plugging Fees: L.D. Drilling, Inc State of Kansas County, Rice, ss. Mike Kelso (Print Name) Employee of Operator or Operator on above-described well

RECEIVED FEB 16 2012

KCC WICHITA

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mike Kelso

AR