

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-20808-000

LEASE NAME Towns

WELL NUMBER 1

SPOT LOCATION SE SE SE

SEC. 9 TWP. 17 RGE. 28(E) or (W)

COUNTY Lane

Date Well Completed _____

Plugging Commenced 2-16-84

Plugging Completed 2-28-84

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Midco Exploration, Inc.

ADDRESS 200 E. 1st, Suite 411
Wichita, Kansas 67202

PHONE # (316)-267-3613 OPERATORS LICENSE NO. 5254

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? One

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	370'	None
				4-1/2"	4649'	1,833.86'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Dumped sand to 4175' and 4 sacks cement Shot casing at 4000', 3500', 3000, 2000' and 1800'. Pulled 69 joints of 4-1/2" casing. Squeezed well with 3 sacks hulls, 10 sacks gel, 50 sacks cement, 15 sacks gel, 1 sack hulls, released plug and pumped 120 sacks 60/40 pozmix cement with 2% added gel and 3% calcium chloride. Maximum pressure was 600 psi and shut in 200 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as **RECEIVED** that the same are true and correct, so help me God.

STATE CORPORATION COMMISSION

Signature) James W. Rockhold

(Address) James W. Rockhold
Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 2nd day of March, 1984

Wichita, Kansas
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

Iona M. Leatherman
Notary Public

My Commission expires: _____